

COUNTY of KANE
PURCHASING DEPARTMENT
KANE COUNTY GOVERNMENT CENTER

Theresa Dobersztyn, C.P.M., CPPB
Director of Purchasing



719 S. Batavia Ave., Bldg. A, 2nd Floor
Geneva, Illinois 60134
Telephone: (630)232-5929
Fax: (630) 208-5107

January 4, 2018

ADDENDUM 2

INVITATION TO BID: #10-019

TITLE: Import of Clean Soils to Settlers Hill

The attention of all bidders is called to the following questions and responses regarding the subject bid document:

1. Please clarify the required import volume. The bid documents/items it states 120,000 CY, however the phased drawing page shows 156,961 CY? ***120,000 CY is the accurate estimation of the remaining soil needed. Explanation: The phasing plan is an estimate of the work that was to be conducted. At the end of 2018, Curran was able to continue operations slightly beyond Phase II. In addition, some soil is currently stockpiled at the top of the hill, this stockpile will not need to be handled by the import hauler.***
2. Bid documents states the County wants the Contractor to ensure 5,000 CY per day for the Curran crews? Is 5,000 CY per day the correct number? ***This should be 2,000 CY per day, not 5,000 CY.***
3. Is the deadline presented in the bid documents to fill the borrow pit area after excavation a firm deadline? ***Option 3: Item 2 states, "Filling of Borrow Source from 08/31/19 – 12/31/22". The County still aims to have the borrow pit fill complete by the end of 2022. However, some flexibility for Item 2 may be considered if inclement weather factors affect the work. The County's main priority is to finish the construction of the cross country course.***
4. What material should the borrow pit be filled in with? ***Option 3: Item 2, "Filling of Borrow Source for Revenue Sharing" should consist of clean fill held to the same standards as the other import for the project.***
5. What is the approximate distance to the dump locations/Curran's working face from the borrow pit area? ***From the borrow pit to Phase 3 is approximately 5,000 ft. From the borrow pit to Phases 4 and 5 is approximately 4,000 ft. Please note there are significant grade changes on these routes. The exact location of placement will be dependent on the location of Curran's current working face, and the contractor/operator hauling the materials will be***

required to coordinate closely with Curran's on site staff to dump in the appropriate location.

Please Note: Borings of the borrow pit are underway but results will not be available until after the bid opening. For the bid, Bidder should assume material available from the borrow pit area meets the requirements for embankment material set forth in the bid documents. If material is found not to meet the requirements for embankment, Option 3 will be removed from award consideration.

Please acknowledge receipt of this addendum in the space provided on Page 28 of the bid document. Thank you for your interest in the Kane County procurement process.

Sincerely,

Maria C. Calamia

Maria C. Calamia, CPPB
Assistant Director of Purchasing